



# Overview of the Magnetic Measurement Activities at Sirius


James Citadini

21<sup>st</sup> International Magnetic Measurement Workshop

24<sup>th</sup> – 28<sup>th</sup> June 2019


- Sirius Project and Status
- Magnetic Measurement Systems
- Measurement Results
  - Quadrupoles and Sextupoles: Rotating Coil Measurements
  - Dipoles: Hall Probe Measurements
- Next Steps


# Sirius Project and Status




## Storage Ring

Beam energy	3.0 GeV
Circumference	518.4 m
Lattice	20 x 5BA
Hor. emittance (bare lattice)	250 pm.rad
Hor. emittance (with IDs)	→ 150 pm.rad
Nominal current, top up	350 mA
Long straight sections	5 x 7.5 m
Short straight sections	15 x 6.5 m
Superbend peak field	3.28 T
Superbend critical energy	19.6 KeV










Phase	Number of beamlines	Status	First Beam
1-A	6	Construction	2019
2*	5	Funding	2020
1-B	7	Design	2021

[wiki-sirius.lnls.br](http://wiki-sirius.lnls.br)

-  **3.2T Superbend**
-  **Short period undulator**
-  **Long period undulator**

\* Mainly refurbished beamlines from the UVX machine



## Magnets installation



## Booster



Splitting the installation time  
with Booster beam tests.





## Storage Ring

(12 sections already assembled  
with vacuum chambers)



Installation of storage ring  
electromagnets already finished

Currently finishing installation of  
the storage ring superbends



NEG coating activation


Vacuum system  
assembling process





Installation of RF cavity solid state amplifiers

Booster out-vacuum septum for injection




## Sirius Carnauba beamline

## Sirius optical clutch




- Booster beam tests (without RF cavity): More than 15000 turns!



Booster stripline signal.

- Schedule:
  - Booster commissioning in July.
  - Storage Ring delivery in early August.
  - Tests of all Sirius subsystems until the end of August.
  - September – First beam in the Storage Ring.
  - January – Startup of the first beam lines.

# Magnetic Measurement Systems



**Two Rotating Coil  
Systems**

**7 meters long  
Hall Probe Bench**


**NMR  
Teslameter**





**Helmholtz Coil System**



**Permeameter**







## Hall Probe Bench


7 m-long granite table

Hall probes calibrated against NMR measurements

Roll, Pitch and Yaw <math>< \pm 15 \text{ mrad}</math>


Horizontal and vertical straightness <math>< \pm 12 \text{ }\mu\text{m}</math>

Longitudinal Linear Error <math>< \pm 6 \text{ }\mu\text{m}</math>




- Air bearings
- 360000 pulses encoder
- Coil mounted on a ceramic tube
- Springs tensioning system for precision assembly





Rotating Coil	Booster	Storage Ring
Unbucked tungsten radial coils		
Number of turns	10	9
External Radius [mm]	18.15	13.013



Coil positioning error:  
 $\pm 0.1$  mrad

# Measurement Results

- Excitation curves measured with the rotating coil systems for all Sirius quadrupoles, sextupoles and slow correctors
- 2D field maps measured for all dipoles with the Hall probe bench
- Sorting algorithm applied to all Booster and Storage Ring electromagnets before installation
- Storage ring fast corrector prototype measured and approved


## External Manufacturer (WEG)

- **LNLS:** simulation, design & magnetic measurement
- **WEG:** manufacturing, quality control, mechanical measurements

Material: Laminated (0.5 mm) Silicon Steel



Storage Ring quadrupole (single pole) measurement at CMM




Mechanical Tolerances:  $\pm 30 \mu\text{m}$


10 micrometer flatness girder

100 MPa compressive strength concrete


5 GPa compressive strength resin



High rigidity levelling units




V 1<sup>st</sup> mode: 268 Hz





H 1<sup>st</sup> mode: 152 Hz

**Multipole Magnets aligned by mechanical definition using reference surfaces of magnets and girder**



	Booster			Storage Ring		
Quadrupole	QF	QD	QS	Q14	Q20	Q30
Number of magnets	50	25	1	70	170	30
Length [m]	0.2	0.1	0.1	0.14	0.20	0.30
Bore diameter [mm]	40	40	40	28	28	28
Maximum Field Gradient [T/m]	18.7	5.2	1.6	37.2	45.4	45.4







The storage ring sextupole has additional coils to provide horizontal and vertical slow dipolar correctors as well as skew quadrupolar field.


Sextupole	Booster	Storage Ring
Number of magnets	35	280
Length [m]	0.1	0.15
Bore diameter [mm]	40	28
Maximum Sextupole Field Gradient [T/m <sup>2</sup> ]	200	2402

## Magnetic center offset for Sirius quadrupoles and sextupoles.




\*Dashed lines are the tolerances: 160  $\mu\text{m}$  for Booster magnets and 40  $\mu\text{m}$  for storage ring magnets.



## Rotation error for Sirius quadrupoles and sextupoles.



**Difference from average strength for Sirius quadrupoles and sextupoles at nominal current.**



## Average residual field for the storage ring sextupoles (S15) at nominal current.






- H-shape dipole
- > 2000 laminations held only by screws.
- Measured with a 1.3 m long L-shaped stem.
- Challenging for stable measurements.





## Booster Dipoles

Number of magnets	50
Length [m]	1.2
Central gap [mm]	28
At extraction energy:	
Field [T]	1.03
Quadrupole gradient [T/m]	2.03
Sextupole gradient [T/m <sup>2</sup> ]	21

## Integrated field and gradients over trajectory for Booster dipoles.



- Magnets with 2 or 3 straight modules
- Modules mounted at angle on the girder
- Same power supply and same pole profile for both magnets





Storage Ring Electromagnetic Dipoles	B1	B2
Number of magnets	40	40
Length [m]	0.85	1.26
Central gap [mm]	24	24
Field [T]	0.564	0.567
Quadrupole gradient [T]	7.58	7.60



- In-house production
- NdFeB permanent magnet blocks
- Low carbon steel for the yoke and low field poles
- Iron-Cobalt for high field poles.



- Peak field of 3.2 T
- 19 keV photon critical energy
- 10% emittance reduction due to superbend longitudinal gradient



Storage Ring Superbend	
Number of magnets	20
Length [m]	0.8
Minimum Gap [mm]	10.2
Peak Field [T]	3.28
Integrated Field [T.m]	-0.75
Integrated Quadrupole Gradient [T]	6.25



Magnetization measurement of the first PM blocks batch with the Helmholtz coils system:

Amplitude error = 0.6 %

Angular error <math>< 1^\circ</math>



Included movable parts for field adjustment in the superbend design to compensate for magnetization errors:

Parameter	Integrated Field Variation [%]	Integrated Gradient Variation [%]
Control Gap	3.1	3.1
Rotating Pole Angle	<math>< 0.06</math>	$\pm 3.8$




Control gap and rotation pole angle for BC magnets after field adjustment.

Integrated field and gradient over trajectory for all storage ring dipoles.



\* Electromagnetic dipoles (B1 and B2) at nominal current.




- **Prototype:** The response frequency attenuation for the fast corrector is -3dB at 11.5kHz
- **Currently under production**

## Storage Ring Fast Correctors


Number of magnets	80
Maximum horizontal and vertical strength	30 $\mu$ rad

## Adjustable Phase Undulators:


APU	
Period [mm]	22
Gap [mm]	7.2
Total length [m]	1.2
Maximum K	1.6



## Delta Undulators:



	Delta 21	Delta 52
Period [mm]	21	52
Gap [mm]	7	14
Total length [m]	2.4	3.6
Maximum K	2.1	5.8



Sirius Delta undulator prototype.

- Extensive temperature tests for the Superbend.
- Measurements and installation of the fast correctors.
- Reassembly and Developments of measurements systems for insertion devices.
- Mechanic and automation tests for the delta prototype.
- Redesign of the keepers and assembly of the first delta prototype.
- Vacuum chamber challenges for installation and NEG coating activation.





IPAC21



**BRAZIL**

*Foz do Iguazu, PR*

*May 23 - 28, 2021*



**Thank you for your attention!**

