



# SOLEIL: Status & Upgrade

Laurent S. Nadolski  
on behalf of the Accelerators and  
Engineering Division



- **SOLEIL 3GLS facility**
  - SOLEIL operational status
  - Selected highlights
  - CoViD-19 challenges on organization and operation
  
- **SOLEIL upgrade Status towards 4GLS**
  - CDR phase
  - Challenges
  - Tentative schedule



Location: France

Circumference: **354 m**


**24 straight sections**

(variable length)



SDL: 4 x **12 m**

SDM: 12 x **7 m**

SDC: 8 x **3.6 m**



**Very compact magnetic structure**



One long straight section (SDL13, accommodating 2 canted long beamlines) has **been modified**

# Beam Time Schedule in 2020

janv 2020	févr 2020	mars 2020	avr 2020	mai 2020	juin 2020	juil 2020	août 2020	sept 2020	oct 2020	nov 2020	déc 2020	janv 2021	févr 2021
mer 01													
jeu 02	01												
ven 03				14									
sam 04													
dim 05													
lun 06													
mar 07													
mer 08													
jeu 09	02												
ven 10													
sam 11													
dim 12													
lun 13													
mar 14													
mer 15													
jeu 16	03												
ven 17													
sam 18													
dim 19													
lun 20													
mar 21													
mer 22													
jeu 23													
ven 24	04												
sam 25													
dim 26													
lun 27													
mar 28													
mer 29													
jeu 30													
ven 31													

COVID-19 lock-down: 7 weeks


U	Uniform
H	Hybrid
8	8 bunches
S	1 bunch
L	Low-Alpha
B	Beamlines
Cp	Periodic radiation safety checks
Tv	Radation safety validation
A	accelerators
.	Shutdown

29 beamlines

Beam availability: 98.7%

MTBF: 100h

Beamline and radiation safety test (4096 hours)  
Beam time according to filling patterns




## Efficiency during beamlines and radiation safety sessions in 2020

3825 hours of beamtime delivered


represent a beam availability of 98.7 %

until the 6th week of RUN 5





# Origin of the 50 hours without beam in 2020

(until the 6th week of RUN 5)




# Preventive and corrective maintenance

## Radiation induced aging of many water cooling hoses



Exuding water along the hose  
(1 drop/sec)





All hoses downstream to dipoles and located on the external side of the tunnel are to be replaced

# An aging facility: increase of flowmeter faults

**Clogging of waterflow reducers** leading to an increase of flowmeter faults

Even with a large cleaning campaign 2 years ago for all the BPMs

**ELETTA flowmeter:** retuning regularly by reaching the lower limit (radiation damage of the membrane ?, calibration), need of a dedicated maintenance or partial replacement after more than 15 years of operation



Eletta Flowmeter

CuO deposit (black) blocking the diaphragms of the 21°C water cooling circuit



## Selected Highlights


Major update  
since ESLS'19


[https://indico.cells.es/event/224/contributions/889/attachments/724/1099/ESLS2019\\_SOLEIL\\_1.pdf](https://indico.cells.es/event/224/contributions/889/attachments/724/1099/ESLS2019_SOLEIL_1.pdf)

- New coupling feedback with white noise
- Multipole Injection Kicker project
- Superbend project
- Photo Desorption “BeamLine”
- New set of beam loss monitors




- Use of noise generator at minimum of coupling (TFB processor) instead of exciting a vertical dispersion wave
  - Step 1: Slow feedback 2 Hz (in operation)
  - Step 2: Fast feedback (to be evaluated)





Installation of the MIK in an available Short Straight Section



Same geometry as the one installed at MAX-IV  
<https://doi.org/10.1016/j.nima.2020.164739>

## Update (since ESLS 2019)

- Ti coating of Sapphire Chamber (ESRF)
- In-house magnetic measurements
- Test of new types of absorbers

## Installation: January 2021 (preparing the upgrade)

- Test the MIK concept on SOLEIL : efficiency, orbit perturbation.
- Test of injection schemes in the framework of the upgrade studies
- On axis Injection with Transverse kick combined with longitudinal kick with the RF

# Dedicated Photo Desorption Beamline for the upgrade

Balance between Photon Stimulated Desorption yield  $\eta$   
 & the NEG Pumping speed / saturation-capacity  
 → For 10 mm diameter chamber ←

## On the ring



- PSD  $\eta$  / Dose of photons
- Activation NEG with SR ?
  - Pumping CH<sub>4</sub>?

What would be the dynamic pressure and its evolution with the photon DOSE

**2 TEST BENCHES @SOLEIL**

## In the LAB

- Intrinsic pumping speed of the NEG  $S^{NEG}$
  - Capacity/saturation
- with Injection gas pure/ $\mu$ leak  
 H<sub>2</sub>, CO, CO<sub>2</sub>, CH<sub>4</sub>.....




First chamber tested (63 mm diameter)  
 Successfully during fall 2020

Characterization bench

# 3T Superbend Project (ROCK BL)


## Permanent magnet dipole (NdFeB)

Length 1.260 m



Gap **16.1 mm**  
B = **2.84 T**


Gap **23 mm**  
B = **1.81 T**



Inside storage ring

A C-shape yoke which allows the removal of the magnet for bake out


Outside the storage ring



Magnet remove device for bake out



Installation: January 2021





Calculation at 8700 mm from the source point for an opening of 13 x 2.4 mm<sup>2</sup>.




Installation in August 2021

Courtesy of Pascale Brunelle



- Average data (13 Hz)
- Turn by turn (injection)
- Fast measurement

Upgrade: radiation safety  
 Measurements vs FLUKA simulations  
 for qualifying the shielding walls





# SOLEIL Upgrade News and Status

Reference:


R. Nagaoka, SOLEIL Upgrade,  
8th Low Emittance Rings Workshop LER2020, INFN-  
LNF, Frascati, Italy, 26-30 October 2020

[https://agenda.infn.it/event/20813/contributions/110195/attachments/76445/98315/SOLEILupgrade\\_LER2020.pdf](https://agenda.infn.it/event/20813/contributions/110195/attachments/76445/98315/SOLEILupgrade_LER2020.pdf)






# Emittance comparison for 3rd and 4th Generation Light Sources on Storage Ring



# CDR Lattice Reference (V0313)

**80 pm.rad    2.75 GeV    354 m    7BA - 4BA**



*Injection*  
 $\beta_x \sim 11m$   
 $L = 7.35m$


$\beta \sim 1.5m$   
 $L = 4.150m$

$\beta \sim 1.1m$   
 $L = 2.730m$

$L = 7.65m$   
 Chicane and  
 quadrupole triplet to  
 be added




**7 BA**



, 16-17


**4 BA**





# General Layout

canted undulators

canted undulators



Entire layout of the CDR lattice: "HOA 7BA-4BA symmetry 2"




	L (mm)	B (T)	G (T/m)	No.	Tot	Location
Short bend 7BA cell	400	0.998	-8.013	24	40	Arcs dispersion suppressor
4BA cell	400	0.957	-8.013	16		
Long bend 7BA cell	947	0.696	-15.88	60	76	In the arcs
4BA cell	947	0.668	-15.88	16		
Rev bend 1 7BA cell	200	-0.210	56.34	120	152	In the arcs
4BA cell	200	-0.201	56.34	32		
Rev bend 2 7BA cell	200	-0.178	57.79	24	40	Arcs dispersion suppressor
4BA cell	200	-0.171	57.79	16		
Quadrupoles [B']	Various	-	$\leq 110$	144	144	Quadruplet in the straights
Sextupoles [1/2 B''] H&V correctors	60/80/110	-	8000 T/m <sup>2</sup> *	368	368	Both arcs and straights Combined magnet
Octupoles [1/6 B'''] Q correctors	50	-	3.10 <sup>5</sup> T/m <sup>3</sup> *	176	176	Both arcs and straights Combined magnet
Total					996	

Main characteristics of the magnets used for the CDR lattice


- Permanent magnets for dipoles and reverse bends
- Need of strong sextupoles and octupoles



Lattice		CDR lattice upgrade	Current lattice
Symmetry		2	1
Energy	[GeV]	2.75	2.75
Circumference	[m]	353.74	354.10
Straight ratio	[%]	24	46
Number of straight secs		20	24
RMS Natural H. emittance	[pm.rad]	81	4000
RMS Coupled H&V Emittance	[pm.rad]	53	
RMS Energy spread	[%]	0.09	0.10
RMS Natural Bunch length	[ps]	9.182	15.17
	[mm]	2.7	
Harmonic number		416	416
Main RF frequency	[MHz]	352.56	352.20
Energy loss per turn W/o ID	[keV]	490	917
RF Voltage	[MV]	1.38	2.9
Momentum compaction factor	[-]	9.12E-05	4.4E-04
Synchrotron frequency	[kHz]	1.4	4.5
	[turns]	600	190
Damping times (H/V/L)	[ms]	7.3 / 13.1 / 11.7	6.9 / 6.9 / 3.5
	[turns]	6000 / 11000 / 10000	5800 / 5800 / 2900
Nominal tunes (H/V/L)		54.2 / 18.2	18.16 / 10.22
Natural chromaticities (H/V)		-108 / -65	-53 / -19
Corrected chromaticities (H/V)		+1.6 / +1.6	+1.3 / +2.2




On-momentum Frequency Map Analysis (FMA) at injection point




Off-momentum Frequency Map Analysis (FMA) at injection point

Left: Local energy acceptance along 1/4 ring




$\tau_{\text{Touschek}}$  at 500 mA:  
 ~3.5 hours **100% coupling**  
 ~1.5 hours 10% coupling  
**w/o bunch lengthening**






Half physical aperture along the ring including in-vacuum insertion device gaps



## Studies of


- Lattice tuning flexibility
- 1<sup>st</sup>-turn steering
- Robustness against errors

launched with specific BPM-correctors (dipolar, normal and skew quadrupolar) configurations



# Top-up Injection schemes developed [1/2]


- Two injection schemes are developed and studied at SOLEIL using a **MIK (Multipole Injection Kicker)**, with the experience of developing one which gave success at MAX-IV: “betatron off-axis” and “synchrotron on-axis” injections




**Left:** Horizontal beta bump for betatron off-axis injection with tunes (54.20, 18.20). **Right:** Horizontal dispersion bump for synchrotron on-axis injection with tunes (54.16, 18.16)

- In both cases, MIK deflection at  $\Delta x = -3.5$  mm from the stored beam location
- Injected beam at  $\delta = -2\%$  for synchrotron on-axis injection

- In both schemes, beam is injected to a ring tuned to a **coupling resonance** and the stored beam is **fully betatron coupled**
- In **betatron off-axis injection**, nonlinear tune shifts with amplitude are adjusted to enable “**dissonance**” for the injected beam



# Injection schemes developed [2/2]



H and V beam envelopes over 900 turns after injection for both injection schemes, w/o error at injection nor in storage ring. Ring working point is set at full coupling.  $(\epsilon_H)_{inj} = (\epsilon_V)_{inj} = 5 \text{ nm.rad}$ ,  $\sigma_L = 25 \text{ ps}$  for betatron and  $35 \text{ ps}$  for synchrotron injections

	Positive aspects	Negative aspects
Betatron off-axis	<ul style="list-style-type: none"> <li>• Allow straightforward implementation in injection straight</li> <li>• Pulse magnets specs comfortable</li> </ul>	<ul style="list-style-type: none"> <li>• Sensitivity to lattice errors</li> <li>• Need of a large DA</li> <li>• Injection beam envelopes have smaller margins against ID gaps</li> </ul>
Synchrotron on-axis	<ul style="list-style-type: none"> <li>• Relaxed DA requirement</li> <li>• Less sensitivity to lattice errors</li> <li>• Reduced injection beam envelopes</li> </ul>	<ul style="list-style-type: none"> <li>• Explicit lattice modifications with a dispersion bump</li> <li>• Need of larger off-momentum DAs</li> <li>• More demanding MIK specs</li> </ul>

⇒ **Both schemes to be pursued further**






# Magnet Prototypes

**Quadrupole = 140 T/m (7 X today) Sextupole = 8000 T/m<sup>2</sup> (25 X today)**


**Extensive use of permanent magnets**

## ➤ Quadrupole

- Procurements by the end of 2020
- In-house assembly by the end of 2020
- Magnetic measurements First semester of 2021




## ➤ Combined dipole (Permanent magnet)




- Assembly and magnetic meas. Mid 2021

## ➤ Multipurpose sextupole



- Assembly and magnetic meas. Mid 2021

## ➤ Multipurpose octupole




- Assembly and magnetic meas. 25 Mid 2021

- 4 reviews held during the last 6 months
  - Ultra-vacuum system review (11-12 June 2020)
  - Magnet Review (2-3 July 2020)
  - Lattice and Injection Review (7-8 September 2020)
  - Girder Review (17-18 November 2020)
- SOLEIL SAC (16-17 November 2020)
- SOLEIL council (14 December 2020)
- Mini-MAC to close the CDR phase (February 2021)



# Tentative Planning and Objectives



- Despite a very special year due to CoViD-19 crisis
  - Operation with extremely good performance (7 weeks operation lock-down)
  - All 29 beamlines work 24/7
  - Small delays concerning major projects of the accelerators
- Upgrade
  - Ending the CDR period:
    - a first strong lattice candidate answering major criteria (performance, impact on shielding, number of BLs)
    - A strong scientific case
  - Preparing TDR phase
    - Entering prototyping phase (magnet, vacuum, girders, injection, diagnostics, RF-system, insertion devices, etc.)
    - **Critical phase for the mechanical integration**, extraction of the photo beams, etc.
    - Robustness and tuning capability of the lattice
    - Choice of ex/in situ backing out, NEG and pumping capacity of 6-10 mm diameter chambers
    - New Booster design
    - ...



# Questions ?

## Acknowledgments

- A. Nadji, R. Nagaoka
- X. Delétoille, J-F. Lamarre
- Accelerator Physics Group

